

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-20043-000

LEASE NAME W.B. Wise

WELL NUMBER 1

SPOT LOCATION C-NW

SEC 33 TWP. 18 RGE. 31 (E) or (W)

COUNTY Scott

Date Well Completed 1972

Plugging Commenced 10-8-87

Plugging Completed 10-12-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Methanol Production Corp.

ADDRESS 165 S. Union Ste. 602, Lakewood, CO 80228

PHONE # (303) 980-1277 OPERATORS LICENSE NO. 043-11

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Krider Depth to top 2779 bottom 2787 T.D. 2816

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	378'	0'
Production				5 1/2"	2813'	2037'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 25 sks. cement to 2650' - pressured to 1000 lbs. Mud to 1400'
Pump 50 sks. cement @ 1400' - Mud to 400'
Pump 40 sks. cement @ 400' - Mud to 40'
Put bridge & 10 sks. cement 40' to 0'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F, Sublette, Ks. 67877

STATE OF Kansas COUNTY OF Haskell

Edgar J. Eves

(Signature) Edgar J. Eves or _____

(Address) Box F, Sublette, Ks. 67877

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____



SUBSCRIBED AND SWORN TO before me this 23 day of Oct., 19 87

Sondra L. Eves
Notary Public

My Commission expires: 12-6-88