

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-20125-0000

LEASE NAME Rueter

WELL NUMBER 1-33

SPOT LOCATION C-SW 1/4

SEC. 33 TWP. 18 RGE. 31 (~~XX~~ or (W))

COUNTY Scott

Date Well Completed 2-14-1977

Plugging Commenced 3-24-1988

Plugging Completed 3-28-1988

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Unico Inc.

ADDRESS Box 35, Farmington, NM 87499

PHONE # (303) 980 1277 OPERATORS LICENSE NO. 3857

Character of Well gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing formation Chase Depth to top 2890 bottom 2920' T.D. 2920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	358'	0'
Production				4 1/2"	2919'	1422'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 20 sks. cement to 2650' and pressured to 500 lbs. - pump 80 sks. cement 1400' to 1200'
Mud 1200' to 370' - pump 40 sks. cement 370' to 270'
Mud 270' to 40' - put bridge and 10 sks. 40' to 3'
Cut off 8 5/8", 3' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
Address Box F, Sublette, KS. 67877

STATE OF Kansas COUNTY OF Haskell, ss.

I, Edgar J. Eves (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well and the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877



MAY 15 1989

5-15-89

CONSERVATION DIVISION
SUBSCRIBED AND SWORN TO
Wichita, Kansas

before me this 10 day of April, 1987

Sondra L. Eves
Notary Public

My Commission expires: 12-6-92