

Rec'd 12-19-1986
COPY

STATE OF KANSAS
GATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,346-0000

LEASE NAME NIEDENS

WELL NUMBER #1-24

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 24 TWP. 17 SRGE. 29 ~~XXXX~~(W)

COUNTY LANE

LEASE OPERATOR LANDMARK OIL EXPLORATION, INC.

ADDRESS 110 S. MAIN SUITE #510, WICHITA, KS. 67202

PHONE# (316) 265-8181 OPERATORS LICENSE NO. 6113

Date Well Completed 12-13-86

Character of Well Dry

Plugging Commenced 12-13-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-13-86

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #1

Is ACO-1 filed? yes If not, is well log attached? on ACO-1

Producing Formation NA Depth to Top _____ Bottom _____ T.D. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface	8 5/8" 23# set	260'	269'	w/160	sxs 60/40	posmix, 2%gel 3%cc

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged @ 2198' w/50 sks, 2nd plug @ 1450' w/80 sks, 3rd plug @ 300' w/50 sks, 4th plug @ 40' w/10 sks, 15 sks in RH, 10 sks in MH. Started 12:30 am. Completed @ 3:00 am
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Warrior Drilling Co. License No. 5883

Address 151 N. Main #700 Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

F.W. Shelton, Jr., (Employee of Operator) ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F.W. Shelton, Jr., Vice Pres.

(Address) 151 N. Main #700 Wichita, Ks. 672

SUBSCRIBED AND SWORN TO before me this 18th day of December, 19 86

Martha E. Gustin
Notary Public



NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

2

Starting Date 11-17-86 month day year

API Number 15-101-21,346-0000

OPERATOR: License # 6113 Name Landmark Oil Exploration, Inc. Address 110 S. Main, Suite 510 City/State/Zip Wichita, Kansas 67202 Contact Person Jeffrey R. Wood Phone 316-265-8181

SW NW NE Sec. 24 Twp. 17 S. Rg. 29 East 4290' West Ft. from South Line of Section 2310 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5883 Name Warrior Drilling Co. City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 330 feet County Lane Lease Name Niedens Well # 1-24 Ground surface elevation feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1-2 X Depth to bottom of fresh water 200 Depth to bottom of usable water 1350 Surface pipe planned to be set 250 Projected Total Depth 4650 feet Formation Mississippi

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext. Air Rotary OWWO Expt X Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. cementing will be done immediately upon setting production casing. Date 11-12-86 Signature of Operator or Agent Jeffrey R. Wood Title President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. This Authorization Expires 5-12-87 Approved By 11-12-86

SPUD 12-6-86

surface pipe - 250' PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

- 1st plug @ B/Anhydrite feet depth with 50 sxs of
2nd plug @ Base Cheyenne feet depth with 100 sxs of
3rd plug @ 30' below surface feet depth with 40 sxs of
4th plug @ 0-40' feet depth with 10 sxs of
5th plug @ feet depth with sxs of
(2) Rathole with sxs
(b) Mousehole with 10 sxs

7:00 am to 11:00 am - 11/17/86

PUSHER Morrison Brewer TD 4650 FORMATION Miss SURFACE PIPE 8 3/8 @ 269 ANHYDRITE 2170 ELEVATION 2782 G6 STARTING TIME & DATE 1:00 am 12-12-86 COMPLETION TIME & DATE 2:00 am 12-12-86 1st PLUG @ 2198 FT. W/ 50 SX 2nd PLUG @ 1450 FT. W/ 80 SX 3rd PLUG @ 300 FT. W/ 50 SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ NO SX CEMENT COMPANY B.G. Dillon 6/9/40/69 TECHNICIAN Paul