

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
300 Bittling Building
Wichita, Kansas

Saline County, Sec 28 Twp 16S Rge (E) 1 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines S/2 SE NE

Lease Owner Beardmore Drilling Company

Lease Name Agin Well No. 1

Office Address 603 Petroleum Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed May 23 1953

Application for plugging filed May 23 1953

Application for plugging approved May 23 1953

Plugging commenced May 23 1953

Plugging completed May 23 1953

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was production obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH
Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 2675 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Shale & Shells		0	123	8-5/8"	123	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

2675' to 120' - Heavy Mud

120' - Wood Plug

120' to 75' - 15 Sacks Cement

75' to 20' - Heavy Mud

20' - Wood Plug

20 to surface - 5 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Beardmore Drilling Company

Address 603 Petroleum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, Heber Beardmore (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore

603 Petroleum Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 1953

My commission expires January 28, 1956

Leonard P. Tolle Notary Public.

23-8390-3 6-51-20M

PLUGGING
FILE SEC 28 T 16 R 12
BOOK PAGE 104 LINE 9

CONSERVATION DIVISION
Wichita, Kansas

AGIN NO. 1

S/2 SE NE
Section 28-16S-1W
Saline County, Kansas

Drilled for: Beardmore, Chapro, Morten
Brown, et al
Drilled By : Beardmore Drilling Company

Casing Record:

8-5/8" 123' w/75 Sacks

Drilling Commenced: May 14, 1953
Drilling Completed: May 23, 1953

Elevation:

DF 1274
GR 1272



<u>FORMATION</u>	<u>DEPTH</u>
Sand	50
Shale	100
Shale - Shells	125
Lime	350
Lime Broken	550
Lime	755
Shale	860
Shale - Shells	1320
Shale - Lime	2010
Lime - Shale	2114
Lime Broken	2185
Lime	2302
Lime - Shale	2635
Shale	2645
Lime	2675 T. D.

D & A

TOPS:

Heebner	1794
Douglas Sand	1828
Brown Lime	1950
Lansing	2003
Mississippi	2643

STATE OF KANSAS

ss

COUNTY OF SEDGWICK

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location-above-described, to the best of my knowledge and belief.

Alb. Beardmore

Subscribed and sworn to before me this 28th day of May, 1953.

Leonard P. Tolk
Notary Public

My Commission Expires: January 28, 1956

RECEIVED
STATE CORPORATION DIVISION
JUN 2 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 28 T 16 R 124
BOOK PAGE 104 LINE 9