

15.169.19168.0000

9

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Saline County, Sec. 28 Twp. 16 S Rge. 1 W (E) (W)

Location as "NE/CNW/SE" or footage from lines SW/4 NE/4 SW/4

Lease Owner Melland Drilling Co.

Lease Name Henry Karber Well No. 1

Office Address 901 North Main, Mc Pherson, Kansas 67460

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 6-25 19 62

Application for plugging filed 10-2 19 71

Application for plugging approved 10-3 19 71

Plugging commenced 10-5 19 71

Plugging completed 10-7 19 71

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 10

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott

Producing formation Depth to top Bottom Total Depth of Well 2609' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		1,727'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 2609' to 2000'. Dumped 5 sx of cement. Mudded hole 150'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the coker.

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.

Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 King St. Hutchinson, Kansas 67501 (Address)

Executed and sworn to before me this 7th day of October, 19 71

My commission expires January 5, 1974

(Signature) Notary Public

15-169-19168-0000

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas

LEASE Henry Karber

WELL NO 1

LOCATION: SW/4 NE/4 SW/4
Sec. 28-16S-1W
Saline County, Kansas

COMPLETED: 6/19/62

COMPLETED:
(rotary) 6/25/62

OPERATOR: F. S. Williams
202 Maltby Building
McPherson, Kansas

CONTRACTOR: William B. King Company, Inc.
1111 North Main Street
Hutchinson, Kansas

CEMENT: 8-5/8" at 130' with 95 sacks of cement
5-1/2" at 2609' with 150 sacks of cement

FORMATION

Surface soil, shale & gypsum	105
Anhydrite	220
Lime & shale	890
Shale & shells	1480
Lime & shale	1808
Sandy lime & shale	1987
Lansing Lime	2010
Lime & shale	2354
Shale	2455
Shale & lime	2600
Mississippi Lime	2609