


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Saline County. Sec. 24 Twp. 16 Rge. 1 ~~XXX~~ (W)  
Location as "NE/CNW&SW&" or footage from lines NW NW SW  
Lease Owner White & Ellis Drilling, Inc.  
Lease Name Beemer Well No. 1  
Office Address Box 448 - El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 4, 1960  
Application for plugging filed February 4, 1960  
Application for plugging approved February 4, 1960  
Plugging commenced February 4, 1960  
Plugging completed February 4, 1960  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2680 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	170'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with heavy rotary mud to 160 ft. Plug at 160 ft. with 1/4 sack hulls and 15 sacks mixed cement thru drill pipe on plug. Hole filled with heavy rotary mud to 30 ft. Plug at 30 ft. with 1/4 sack hulls and 8 sacks cement on plug. Rat hole bridged and capped with 1/2 sack hulls and 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 6 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor White & Ellis Drilling, Inc.  
Address Box 448 - El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
Dale R. Daniel (employee of owner) ~~XXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale R. Daniel

(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of February, 1960

Ernest Siffard

Notary Public.

My commission expires May 21, 1960



15-169-00184-0000

R

8 5/8

170' (Clear bed w/12" sand)

Section: 24-135-11-1  
Saline County, Kansas  
Plotted Base: 51  
V.L.P. (Shale & Shale, Central  
Correlation: 3118 & 3119, Ditch, No.  
Elev. of: 1700/50  
Clear Bed: 214/50  
State Plate: 1305 - 1309 N.E.

7.00' 2500'

Key to Bushing (Shale & Sand) (Shale & Sand) (Shale & Sand)

FORMATION	DEPTH
Soil	0-8
Shale	60
Shale & Shales	100
Lime & Shale	230
Shale & Red rock	250
Lime & Shale	360
Lime	400
Shale w/Lime shls.	560
Lime	595
Shale w/Lime shls.	675
Shale & Shales	740
Shale (sticky)	785
Shale & Lime	857
Shale & Red rock	141
Shale & Lime	369
Shale	419
Shale w/Lime	463
Sand & Shale	495
Lime	546
Shale & Lime	553
Lime w/Shale shls.	723
Lime	780
Shale & Lime	842
Sand (M.S.C.)	
Shale & Shales	1000
Lime	1086
Shale & Lime	1195
Lime	1240

7425

Peabody	1281
Comanche	1405
Douglas Sand	1512
Brown Lime	1548
Lawling	1600
Base Kansas Sand	1605
Burgess Sand	1781
Mississippi	1846

RECEIVED  
STATE CORPORATION COMMISSION

JUN 6 1960

CONSERVATION DIVISION  
Wichita, Kansas

Checked by: [unclear]  
Plotted by: [unclear]