

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-101-21,499-0000

LEASE NAME Boomhower

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

WELL NUMBER #2-36

330 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR VESS OIL CORPORATION

SEC. 36 TWP. 17S RGE. 29 (E) of (W)

ADDRESS 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

COUNTY LANE

PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030

Date Well Completed 3/2/89

Character of Well OIL

Plugging Commenced 8/18/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/18/00

The plugging proposal was approved on 08/02/2000 (date)
by Mike Maiers (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Ft. Scott / Johnson Depth to Top 4458 Bottom 4532 T.D. 4611

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		Casing Record				
Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	261	-----
				4-1/2"	4610	-----
				Port collar - 2157'		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Connected to 4-1/2" and pumped 50 sx 60/40 poz w/6% gel and 300# hulls; 30 bbls gel spacer. Pressure dropped from 500 psi to 0 psi. Followed w/120 sx same cement. Cement top 650'. Connected to 4-1/2" and 8-5/8" annulus and pumped 5 sx cement - 500#. Pumped 30 sx cement down 4-1/2" casg. Came back and topped off casing w/30 sx cement.

Approved by Mike Maiers
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Swift Services, Inc.

Address P.O. Box 466, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ken Rupp

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Pat Canaday (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address)

SUBSCRIBED AND SWORN TO before me this


8100 E. 22nd St. N., Bldg. 300
Wichita, KS 67226
23rd day of August 2000

Notary Public

My Commission Expires:



Form CP-4
Revised 05-88



OPER Mess Oil Corp

WELL NO. # 1

LEASE Boomhower

JOB TYPE Plug to Abandon

TICKET NO. 2708

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	07:00							Called out
	08:00							On location (set up) take
	09:15							Break off head
	09:30							Start cont
								50 sks w/ 300# Halls
								30 bbls gelled spacer
								Hole fouled & pressure so 500PSI
								Pressure disappeared 4 hours after
								Pumped 150 sks cont
								no pressure
								Let static out 650ft to fluid
								Pumped 1 bbl down casing - broken head
								& pressure to 500PSI
								Released pressure.
								Pumped 30 sks down casing
								Static out 650ft down
	10:40							Shut down
								will come back next week
								& top off with 30 sks
								205 sks cont
								10 sks gel
								30 sks to top off with later

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 24 2000
 CONSERVATION DIVISION
 Wichita, Kansas

SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

Invoice

DATE	INVOICE #
8/18/00	2708

RECEIVED

AUG 23 2000

BILL TO
Vess Oil Corporation 8100 E. 22nd St. N. Bldg 300 Wichita, KS 67226

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	# 1	Boonhower	Lane	none	Oil	Workover	Ted	PTA
PRICE REFERE...	DESCRIPTION				QTY	UNIT PRICE		AMOUNT
575W	Milage				30	2.50		75.00T
576W-P	Pump Charge - PTA				1	500.00		500.00T
275	Cotton Seed Hulls				3	15.00		45.00T
279	Bentonite Gel				10	11.00		110.00T
328	Swift Light 60/40 Pozmix (6% gel)				235	5.65		1,327.75T
581W	Service Charge Cement				245	1.00		245.00T
583W	Drayage				317.82	0.75		238.37T
580	Additional hrs.				1	100.00		100.00T
	Subtotal							2,641.12
	Sales Tax					4.90%		129.41
Thank you for your business.							Total	\$2,770.53