

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
30 S. Market, Room 2019  
Vichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-21,443-00-00

LEASE NAME Boomhower

WELL NUMBER # 2

3630 Ft. from (S) Section Line

2970 Ft. from (E) Section Line

SEC. 36 TWP. 17 RGE. 29  or

COUNTY Lane

Date Well Completed 1/9/88

Plugging Commenced 1/16/2002

Plugging Completed 1/16/2002

RECEIVED  
JAN 22 2002  
1-22-02  
CONSERVATION DIVISION  
Vichita, Kansas  
TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR MIDCO Exploration, Inc.

ADDRESS 414 Plaza Drive, Suite 204

PHONE# (630) 655-2198 OPERATORS LICENSE NO. 5254

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/15/2002 (date)

by Myers - Dodge City Office (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing/Miss-- Depth to Top 4144 Bottom 4563 T.D. 4593

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing.	oil/water	4144	4292	8 5/8	278	-0-
Mississippi	oil/water	4546	4563	5 1/2	4649	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set:

Pumped 100 pounds of hulls followed by 50 sks cement with 200 lbs hulls;  
mixed and pumped 18 sacks gel in gel water spacer; followed by 200 sks cement to surface.

Name of Plugging Contractor Plains, Inc. License No. 04072

Address Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: MIDCO Exploration, Inc.

STATE OF Illinois COUNTY OF DuPage, ss.

Earl J. Joyce, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well is filled the the same are true and correct, so help me God.

(Signature) *Earl J. Joyce, Jr.*

(Address) 414 Plaza Drive, Suite 204 Westmont

SUBSCRIBED AND SWORN TO before me this 18th day of January, 2002 ~~XX~~

Nancy L. Macyunas  
Notary Public Nancy L. Macyunas

My Commission Expires: 6/24/2002-IL

Or