

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-101-21404-0000

LEASE NAME Riley B

WELL NUMBER #1 SWD

2310 Ft. from S Section Line
2970 Ft. from E Section Line

SEC. 36 TWP. 17S RGE. 29 (E) or (W)

COUNTY LANE

Date Well Completed 3/10/88

Plugging Commenced 2/4/00

Plugging Completed 2/4/00

RECEIVED
KANSAS CORP COMM

2000 FEB 22 2:04
2-22-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01/24/2000 (date)
by David Williams (KCC District Agent's Name)

Is ACO-1 filed? NO If not, is well log attached? na

Producing Formation Cedar Hil Depth to Top 1720 Bottom 1820 T.D. 4633

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		Casing Record				
Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	375	-----
				5-1/2"	4632	-----
Perforated and squeezed: 2150' w/150 sx; 1320 w/150 sx; 760' w/200 sx						
pumped 100 sx down 8-5/8" and 5-1/2" annulus						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Pumped down 5 1/2" csg w/200# hulls; 50 sx 60/40 Poz w/6% gel w/300# hulls;
100 sx 60/40 Poz w/6% gel. Max pressure - 500#. SIP - 500#. Connect to 8-5/8" and pumped
3/4 barrel of same cement. Pressured to 500# and held. Approved by Mike Maiers w/KCC

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Swift Services, Inc. License No. _____

Address P.O. Box 466, Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ken Rupp

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Pat Canaday (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts,
statements and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature)

(Address)

8100 E. 22nd St. N., Bldg. 300
Wichita, KS 67226

SUBSCRIBED AND SWORN TO before me this 18th day of February 2000

My Commission Expires:



Notary Public

Form CP-4
Revised 05-88



CHARGE TO: Ness Oil Corp.
 ADDRESS:
 CITY, STATE, ZIP CODE: Wichita KS

TICKET No 1918

PAGE 1 OF 1

SERVICE LOCATIONS 1. <u>Ness City</u>	WELL/PROJECT NO. <u>SWD</u>	LEASE <u>Riley "B"</u>	COUNTY/PARISH <u>Lane</u>	STATE <u>KS</u>	CITY	DATE <u>2-4-2000</u>	OWNER <u>same</u>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO.	SHIPPED VIA	DELIVERED TO <u>N.W. Dighton</u>	ORDER NO.	
3.	WELL TYPE <u>Disposal</u>	WELL CATEGORY <u>Abandoned</u>	JOB PURPOSE <u>P.T.A</u>	WELL PERMIT NO.	WELL LOCATION		
4.	REFERRAL LOCATION	INVOICE INSTRUCTIONS					

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575					MILEAGE	104	35	mp		2.00	70.00
576					Pump Charge		1	EA			450.00
328					60/40 6% Hel		150	SKS		5.55	832.50
275					Cottonseed Hulls		5	SKS		15.00	75.00
581					Bulk Service Charge		300			1.00	300.00
583					Drayage		449	93	Ton MP	.75	337.44

RECEIVED
 KANSAS CORP CORP
 2000 FEB 22 10 24 05

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X Kenning [Signature]
 DATE SIGNED 2-4-2000 TIME SIGNED 0900
 A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN? WE UNDERSTOOD AND MET YOUR NEEDS? OUR SERVICE WAS PERFORMED WITHOUT DELAY? WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY? ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO <input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	2064.94
				TAX	101.18
				TOTAL	2166.12

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES: The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR Lenny APPROVAL

Thank You!