

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,280-0000

LEASE NAME Riley A

WELL NUMBER 1

SPOT LOCATION C NE SW

SEC. 35 TWP. 17 RGE. 29 (E) or (W)

COUNTY Lane

Date Well Completed 1-28-86

Plugging Commenced 1-28-86

Plugging Completed 1-28-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR White & Ellis Drilling, Inc.

ADDRESS 401 E. Douglas, Suite 500, Wichita, KS 67202

PHONE # (316) 263-1102 OPERATORS LICENSE NO. 5420

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. 4650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size 8 5/8	Put In 379'	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Spotted 50 sx cement @ 2210' thru drill pipe

Spotted 80 sx cement @ 1340' thru drill pipe

Spotted 50 sx cement @ 410' thru drill pipe

Spotted 10 sx cement @ 40' thru drill pipe

Spotted 15 sx cement in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ernest Sifford

(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 7th day of February, 19 86



RECEIVED
STATE CORPORATION COMMISSION
David F. Jamis
Notary Public

My Commission expires:

FEB 10 1986
02-10-1986
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas
NOTICE OF INTENTION TO DRILL
 (see rules on reverse side)

CARD MUST BE TYPED

CARD MUST BE SIGNED

Starting Date: 1 18 86
 month day year

API Number 15- 101-21,280-0000 *yes*

OPERATOR: License # 5420
 Name White & Ellis Drilling, Inc.
 Address 401 E. Douglas - Suite 500
 City/State/Zip Wichita, Ks. 67202
 Contact Person Micheal W. Dixon
 Phone (316) 263-1102

App. C NE SW Sec 35. Twp 17. S, Rge 29. East West

1790. Ft North from Southeast Corner of Section
 3370. Ft West from Southeast Corner of Section
 (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5420
 Name White & Ellis Drilling, Inc.
 City/State Wichita, KS. 67202

Nearest lease or unit boundary line 730' feet.
 County Lane
 Lease Name Riley "A" Well# 1
 Domestic well within 330 feet: yes no
 Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 XX Oil Swd Infield XX Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 120 feet
 Lowest usable water formation *Dakota*
 Depth to Bottom of usable water *1050* feet
 Surface pipe by Alternate: 1 2

If OWWO: old well info as follows:
 Operator
 Well Name
 Comp Date Old Total Depth 4600
 Projected Total Depth
 Projected Formation at TD Mississippi
 Expected Producing Formations L/KC - Miss.

Surface pipe to be set 360' feet
 Conductor pipe if any required None feet
 Ground surface elevation N. A. feet MSL
 This Authorization Expires 7-14-86
 Approved By 1-14-86 *R*

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging to K.C.C. specifications.

Date 1-14-86 Signature of Operator of *Micheal W. Dixon* Title Geologist *MO*
 Form C-1 4/84

move in 1-21-86 set 360' of 8 5/8

RECEIVED
 STATE CORPORATION COMMISSION


JAN 30 1986 01-30-1986

CONSERVATION DIVISION

D+A

PUSHER *Judy*
 TD 4650' FORMATION *Miss.*
 SURFACE PIPE 8 5/8" @ 379'
 ANHYDRITE 2183' ELEVATION
 STARTING TIME & DATE
 COMPLETION TIME & DATE 6:45 PM 1-28-86
 1st PLUG @ 2210' FT. W/ 50 SX
 2nd PLUG @ 1340' FT. W/ 80 SX
 3rd PLUG @ 410 FT. W/ 50 SX
 4th PLUG @ 40 FT. W/ 10 SX
 RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ SX

CEMENT COMPANY *Allied*
 TECHNICIAN *D.G.*
1st aug 1 w/ 50
2nd chrylene Base w/ 80
3rd Base + 30' w/ 5-0
4th 40-0 SB-10
circ 15' cat
60/40 w/ 6 7/8 gell



15-101-21280-0000

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: White & Ellis Drilling, Inc.
 401 E. Douglas, Suite 500
 Wichita, Kansas 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
 Wichita, Ks. 67202

Lease Name Riley A Well No. 1

Sec. 35 T. 17S R. 29W Spot C NE SW

County Lane State Kansas Elevation

Casing Record:

Surface: 8 5/8 @ 379' with 3%cc 2%gel 235 sx.

Production: @ with sx.

Type Well: D & A Total Depth 4650'

Drilling Commenced 1-21-86 Drilling Completed 1-28-86

Formation	From	To	Tops
Cellar	0	7	Anhydrite -2183
Sand, Shale	7	2183	
Sand, Shale, Lime	2183	2622	
Shale, Lime	2622	3422	
Lime, Shale	3422	3994	
Lime	3994	4100	
Lime	4100	4250	
Shale, Lime	4250	4355	
Lime	4355	4445	
Lime, Shale	4445	4650	

02-10-1986

RECEIVED
STATE CORPORATION COMMISSION

FEB 10 1986

CONSERVATION DIVISION
Wichita, Kansas