


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Flat

Lane \_\_\_\_\_ County. Sec. 19 Twp. 17s Rge. 29W(E) (W)  
Location as "NE/CNW/SW" or footage from lines C of EL NW SW  
Lease Owner Jocelyn & Varn  
Lease Name Floyd Well No. 2  
Office Address 310 K F H Building - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced \_\_\_\_\_ August 3 19 54  
Plugging completed \_\_\_\_\_ August 8 19 54  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4431 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2"	4427'	2698'
				8-5/8"	242'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand from 4431' to 4330' and ran 5 sacks of cement. Mudded hole to 252', set a 10' rock bridge and ran 20 sacks of cement at 242'. Mudded hole to 35' and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Stewart Varn (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stewart Varn  
310 K.F.H. Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 54

My commission expires January 30, 1957

Margaret Sherman Notary Public.  
THE CORPORATION COMMISSION

PLUGGING  
FILE SEC-19 T-17 R-296  
BOOK PAGE 50 LINE 45

SEP 14 1954  
09-14-1954  
CONSERVATION DIVISION  
Wichita, Kansas

HUGOTON PRODUCTION COMPANY  
 Box 441  
 Garden City, Kansas

15-101-06026-0000

Company: HUGOTON PRODUCTION CO.  
 Farm: Floyd No. 2

Sec. 19 T. 17S R. 29W  
 C E $\frac{1}{2}$  NW SW

Total Depth. 4430

Comm. 11-21-52

Comp. 1-9-53

County Lane

Shot or Treated.

Kansas

Contractor. Glenn R. Nye Drlg. Co.

Elevation. 2835.5 K.B.

Issued.

CASING: 8 5/8" 242' w/250 sx cem.  
 5 1/2" 4427' w/50 sx cem.

Figures Indicate Bottom of Formations

surface sand & clay	0-40
sand	200
shale	247
shale	1000
sand & shale	1150
shale	1250
red bed, shale & sand	1610
shale & shells	1678
anhydrite	1705
red bed & shale	2230
shale, salt and anhydrite	2390
shale	2510
shale & red bed	2570
shale & lime	2905
lime & shale	4085
lime	4135
lime & shale	4430

DST No. 1 4316-4345

Tool open 1 HR

B.H.P.-0

Rec. 2" drlg. mud

Core No. 1 4315-4345

Core No. 2 4400-4430

DST No. 2 4401-4430

Tool open 1 HR

B.H.P.-1120#

Rec.-100' oil and gas  
 cut mud. 120' oil  
 1020' gas

Anhydrite 2228

Heelner 3921

Lans-K.C. 3956

DST No. 3 4396-4422

Tool open 1 HR

B.H.P.-290#

Rec. 30' heavy oil cut mud

09-27-1954

**PLUGGING**  
 HME SEC 19 T 17 R 29 W  
 S00X PAGE 50 LINE 45