

15-101-190340001

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Lane _____ County. Sec. 16 Twp. 17 Rge. 29 (E) _____ (W)

Location as "NE/CNW/SW" or footage from lines ne se

Lease Owner Oil & Gas Property Management

Lease Name Boomer Well No. 1

Office Address 6 th Floor - O & I Life Building Houston, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed _____ 19 65

Application for plugging filed 5-25 19 65

Application for plugging approved 5-28 19 65

Plugging commenced 6-30 19 65

Plugging completed 7-2 19 65

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2900' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	265	None
				4 1/2	2829	2564

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mix 10 sacks cement to plug off perforrations at 2772' - stop plug at 2700. Pull pipe to 660' and circulate gell. Spot 20 sacks cement at 570'. Mud to 230' and 20sacks cement at 230'. Mud to 35' and bridge and 10 sacks cement 35' to cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1965
07-13-1965
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Sargent's Casing Pulling Service
Address Box 506 Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.
Donald W. Jackson (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald W. Jackson
1411 N. Carlton Ave., Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of July, 1965

My commission expires 12-28-68 Notary Public.

WELL LOG
 SUN OIL COMPANY
 S. Boomhower No. 1
 NE/4 SE/4
 Sec. 16, Twp. 17S, Rge. 29W
 Lane County, Kansas

1510119034-0001

<u>Formation</u>	<u>From</u>	<u>To</u>	Drilling Commenced 4-8-63
			Drilling Completed 4-20-63
Surface clay, sand and shale	0	275	Casing Record:
Lime, sand, shale	275	1175	
Shale w/l.s. strks.	1175	2560	8-5/8" at 265' w/200 sax cement.
Lime and shale	2560	3421	
Shale, sand, lime	3421	3694	
Lime and shale	3694	4525	Electric Log Tops:
Shale and sand	4525	4585	
Lime	4585	4712	Pennsylvania 3421'
	T.D.		Topeka 3694'
Dry and Abandoned.			Heebner 3931'
			Lansing-Kansas City 3972'
			Marmaton 4322'
			Cherokee 4525'
			Mississippi 4585'

I hereby certify that the foregoing is a true and correct copy of S. Boomhower No. 1 well log as recorded on the books of Sun Oil Company, Tulsa, Oklahoma

J. H. Allen
 J.H.Allen, Asst.Prod.Supt.

STATE OF OKLAHOMA))
 COUNTY OF TULSA) SS

Subscribed and sworn to before me this 23rd day of April, 1963

W. F. Goodner
 Notary Public

My Commission Expires:
JUN 28 1964

RECEIVED
 STATE CORPORATION COMMISSION
 APR 25 1963
 CONSERVATION DIVISION
 Wichita, Kansas