

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

Anderson # 1
SE SE NE Sec. 26
Twp 19, Rge 20W
Rush County, Kansas.

Locate well correctly on above
Section Plat

Rush County. Sec. 26 Twp. 19 Rge. 20 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Aurora Gasoline Company
Lease Name Anderson Well No. 1
Office Address 308 Wright Bldg, Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-23 19 54
Application for plugging filed 5-22 19 54
Application for plugging approved 5-22 19 54
Plugging commenced 5-23 1:00 A. M. 19 54
Plugging completed 5-23 5:00 A. M. 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4542 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Post Rock, Shale, Shells		0	190'	8 5/8	190'	None
Sand, Shale, Shells, Redbed		190	1390			
Anhydrite		1390	1420			
Shale & Lime		1420	4290			
Cherty Cong & Lime		4290	4502			
Arbuckle		4502	4542			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 175' stirred pits well, ran 1/2 sack hulls and 15 sacks of cement set wood plug, mud to 35'. Ran 1/2 sack hulls and 10 sacks of cement top plug wired (Wood Plug)

STATE CORPORATION COMMISSION

5-27-54
CONSERVATION DIV.
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strain Drilling Company
Address Box 188 Hays, Kansas.

STATE OF KANSAS, COUNTY OF ELLIS, ss.
T. C. Strain (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

Box 188 Hays, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 19 54

My commission expires March 26, 1956

Notary Public.



WELL LOG

COMPANY: Aurora Gasoline Co.

SE SE NE Sec. 26
Twp 19S, Rge 20W
Rush County, Kansas.

LEASE: Anderson # 1

ELEVATION: 2194 R. B.

NOTE: All meas Rotary Bushing

0 50 Post Rock
50 85 Shale & Post Rock
85 190 Blue Shale & Shells
190 600 Shale & Shells
600 650 Shale & Shells
650 800 Sand & Shale
800 1020 Sand
1020 1390 Redbed
1390 1405 Anhydrite
1405 1420 Anhydrite
1420 1710 Shale & Shells
1710 1820 Shale & Shells
1820 1960 Shale & Salt
1960 2010 Shale & Lime
2010 2190 Shale & Lime
2190 2250 Shale & Lime
2250 2275 Lime
2275 2405 Lime & Shale
2405 2520 Shale & Lime
2520 2590 Lime & Shale
2590 2695 Shale & Lime
2695 2790 Shale & Lime
2790 2855 Lime & Shale
2855 3020 Shale & Lime
3020 3165 Lime & Shale
3165 3200 Lime
3200 3300 Lime & Shale
3300 3417 Shale & Lime
3417 3540 Shale & Lime
3540 3650 Shale & Lime
3650 3745 Shale & Lime
3745 3795 Shale & Lime
3795 3860 Lime
3860 3910 Lime
3910 3950 Lime
3950 3985 Lime
3985 4045 Lime
4045 4090 Lime
4090 4145 Lime
4145 4175 Lime & Shale

4175 4240 Lime & Shale
4240 4290 Lime & Shale
4290 4305 Cherty Cong.
4305 4325 Lime & Chert
4325 4365 Lime & Chert
4365 4405 Lime & Chert
4405 4440 Lime & Chert
4440 4480 Lime & Chert
4480 4502 Lime & Chert
4502 4515 Arbuckle
4515 4542 Arbuckle
4542 (Total Depth)

COMMENCED: 5-8-54

COMPLETED: 5-23-54

CASING RECORD:

8 5/8" Surface Casing set @ 190' W/135
sacks of cement by Halliburton.

D.S.T. by Western Testers

4501 to

4542 Tool open 1 hour. Recovered

3250' salt water 15 min. B. H. P. 1540#

I.F.P. 1060# F.F.P. 1540#

Run Schlumberger Log

Geologist: David LeCount Evans.

TORS:

Geological

Anhydrite	1390 (+804)	Cherokee	4170 (-1976)
Heebner	3716 (-1522)	Cherokee Sand Stone	4234 (-2040)
Toronto	3737 (-1542)	Cherty Cong.	4266 (-2072)
Lansing K. C.	3701 (-1570)	Miss. Chat	4299 (-2105)
Base K. C.	4070 (-1876)	Miss Lime	4340 (-2146)
		Viola	4406 (-2212)
		Simpson	4491 (-2297)
		Arbuckle	4502 (-2308)
		R. T. D.	4542 (-2348)

STATE OF KANSAS)SS
COUNTY OF ELLIS)I hereby affirm that the above and foregoing is a true and correct copy of the log of
the Anderson # 1, located SE 1/4 Sec. 26, Twp 19S, Rge 20W. Rush County, Kansas.

STATE CORPORATION COMMISSION

MAY 27 1954

CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR S. Rain Drilling Company

BY: S. Rain

Subscribed and sworn to before me this 26th day of May 1954
My commission expires March 26, 1956

PLUGGING
FILE SEC 26 T 19 R 20W
BOOK PAGE 36 LINE 27

Notary Public.