


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

15-165-30378-0000

WELL PLUGGING RECORD

Rush County, Sec. 25 Twp. 19 Rge. 20 (E) W (W)
Location as "NE/CNW&SW&" or footage from lines SW SW SE
Lease Owner Aurora Gasoline Company, Etal
Lease Name Hass Well No. 1
Office Address 1107 Union Natl. Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 27 1958
Application for plugging filed " 19"
Application for plugging approved " 19"
Plugging commenced " 19"
Plugging completed " 19"
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, 805 Main Street, Victoria, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4652 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Surface Hole</u>	<u>Water</u>	<u>0</u>	<u>565</u>	<u>5 5/8"</u>	<u>565</u>	<u>None</u>
<u>See Attached Log</u>						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud from 4652 to 540': Bridge at 540' with 20 Sacks of cement.

Filled with mud to 240': Bridge at 240' with 20 Sacks of cement.

Filled with mud to 40' with 10 Sacks of cement cap.

RECEIVED

APR 24 1958
4-24-58
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bex & Morris Drilling Company
Address Box 334, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
C. E. McClure (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

C. E. McClure

Bex 334, El Dorado, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 58

My commission expires July 23, 1960

Winifred E. Cruit

Winifred E. Cruit

Notary Public.

PLUGGING
FILE SEC 26 T 19 R 20 W
BOOK PAGE 91 LINE 26

15-165-30378-0000

Elevation 2279 DV

2282 KB

HAAS WELL # 1

AURORA GASOLINE CO. ET AL

Total Depth 4652
 Contractor Rex & Morris Drilling Co.
 Commenced 3-12-58
 Completed 3-27-58
 Initial Production D & A

Location - NE SE SE
 Section - 25-198-20W
 Rush County, Kansas.

Casing Record:
 8 5/8" @ 565' w/ 300 sacks

FORMATION

DEPTH

Surface Hole	565
Shale & Shale & Red Bed	865
Sand & Shale	1080
Shale & Red Bed	1435
Shale, shale and salt	1950
Shale & Lime	2190
Lime & Shale	2650
Shale & Lime	2750
Lime and Shale	3220
Lime	3313
Lime & Shale	3480
Lime	3600
Shale & Lime	3740
Lime & Shale	3890
Lime	4249
Shale & Sand	4272
Sand & Shale	4286
Conglomerate	4329
Lime	4371
Shale & Lime	4610
Lime	4652 TD

RECEIVED
 STATE CONSERVATION COMMISSION

APR 24 1958
 4-2458
 CONSERVATION DIVISION
 Topeka, Kansas

Ran Walex Radiation Guard Log

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Carl D. Koontz

Title Geologist

STATE OF KANSAS)
) SS.
 COUNTY OF BUTLER)

Subscribed and sworn to before me, a Notary Public, this 23rd day of April 1958.

Winfred E. Crut
Winfred E. Crut - Notary Public

My commission expires:

July 23, 1960.

PLUGGING
 FILE SEC 25 T 19 R 20 W
 BOOK PAGE 91 LINE 26