

API NUMBER 15-165-21651-0000

LEASE NAME Bannister

WELL NUMBER #1

330 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 21 TWP. 19 RGE. 20 (E) or (W)

COUNTY Rush

Date Well Completed 4-07-90

Plugging Commenced 4-07-90

Plugging Completed 4-07-90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Argent Exploration, Inc.

ADDRESS 110 S. Main, Suite 810 Wichita, KS. 67202

PHONE(S) (316) 262-5111 OPERATORS LICENSE NO. 31283

Character of Well D&A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-07-90 (date)

by Duane Rankin (KCC District Agent's Name).

Is KCC-1 filed? by operator If not, is well log attached? yes

Producing Formation --- Depth to Top --- Bottom --- T.O. 4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	297	8 5/8"	297	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from    feet to    feet each set

50 sx. @ 1550', 50 sx. @ 820', 50 sx. @ 350', 10 sx. @ 40', 15 sx. in rathole

Total: 175 sx. 40/60 poz. 6% Gel

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Argent Exploration, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis

(Employee of Operator Argent Exploration, Inc.) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) [Signature]

L. D. Davis


(Address) R.R. 1 Box 183 B Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 12th day of April, 19 94

[Signature]  
 Notary Public

Bessie M. DeWerff

My Commission Expires: 5-20-97



RECEIVED  
 STATE CORPORATION COMMISSION  
 4-13-94  
 APR 13 1994  
 CONSERVATION DIVISION  
 Wichita, Kansas

DRILLER'S WELL LOG

COMMENCED: 3-31-94  
COMPLETEE: 4-07-94

0 - 297 Shale  
297 - 535 Sand & Shale  
535 - 1210 Shales & sand  
1210 - 1700 Shale  
1700 - 4450 Lime & Shale

ARGENT EXPLORATION, INC.  
BANNISTER #1  
N/2 NE NW Sec. 21-19S-20W  
RUSH COUNTY, KANSAS  
ELEVATION: 2294 GR 2299 KB

SURFACE CASING:  
8 5/8" set @ 297' W/185 sx. 60/40  
Pozmix, 2% Gel 3% cc

A F F I D A V I T

STATE OF KANSAS     )  
COUNTY OF BARTON   )SS

L. D. DAVIS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.