


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rush County, Sec. 3 Twp. 19 Rge. (E) 20 (W)

Location as "NE/CNW&SW&" or footage from lines NE SE NW

Lease Owner Abercrombie Drilling, Inc.

Lease Name KUFELD

Well No. 1

Office Address 801 Union Center, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 16, 1972

Application for plugging filed (verbally) May 16, 1972

Application for plugging approved (verbally) May 16, 1972

Plugging commenced May 16, 1972

Plugging completed May 16, 1972

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 4310 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug was set at 550' w/50 sx.

2nd plug was set at 240' w/15 sx.

Top plug was set at 40' w/8 sx.

Put 2 sx. in rat hole. Job completed at 10:30 p.m. 5-16-72.

RECEIVED
STATE CORPORATION COMMISSIONMAY 25 1972
5-25-72
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jerry A. Langrehr

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 1972

My commission expires February 10, 1975

Beverly Mann
Beverly Mann

Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	KUFELD #1
LOCATION:	NE SE NW, Sec. 3-19S-20W Rush County, Kansas
GEOLOGIST:	Jack K. Wharton
SPUD DATE:	May 6, 1972
COMPLETION DATE:	May 16, 1972

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1972
5-25-72
CONSERVATION DIVISION
Wichita, Kansas

0	165	Clay, rock and shale
165	286	Shale and rock
286	800	Shale
800	1030	Sand
1030	1404	Shale
1404	1435	Anhydrite
1435	2108	Shale
2108	2205	Shale & Lime
2205	2285	Shale
2285	2540	Lime & Shale
2540	2630	Shale & Lime
2630	2925	Lime
2925	3940	Lime & Shale
3940	4028	Lime
4028	4080	Lime & Shale
4080	4298	Lime
4298	4310	Lime and Chert
	4310	Rotary Total Depth

Drilled 286' of 12½" surface hole. Set 8-5/8" surface casing at 276' cemented w/175 sx. Sunset cement. Cement circulated. Plug was down at 3:00 a.m. 5-6-72.
Dry and Abandoned

ELECTRIC LOG TOPS		ELEVATION
Anhydrite	1402 (+ 770)	
B/Anhydrite	1444 (+ 738)	2172 K.B.
Heebner	3653 (-1481)	2170 D.F.
Toronto	3670 (-1498)	2164 G.L.
Lansing	3698 (-1526)	
B/K.C.	4014 (-1842)	
Pawnee	4070 (-1898)	
Cherokee Shale	4144 (-1972)	
Cherokee Sand	4220 (-2048)	
ELTD	4305 (-2133)	

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KUFELD #1, NE SE NW, Section 3-19S-20W, Rush County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
Jerry A. Langrehr
Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 23rd day of May, 1972.

Beverly Mann
Beverly Mann, Notary Public

My Commission Expires:

February 10, 1975