

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-165-21,621-00-00

LEASE NAME Brack

WELL NUMBER 1

4620 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 3 TWP. 19 RGE. 20 ~~W~~ or (W)

COUNTY Rush

Date Well Completed 11/20/92

Plugging Commenced 11/20/92

Plugging Completed 11/20/92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS P.O. Box 8647, Wichita, KS 67208

PHONE# (316) 681-0231 OPERATORS LICENSE NO. 8061

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/19/92 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filled? yes If not, Is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4230 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation Surface	Content	From 257'	To 0'	Size 8-5/8"	Put in 257'	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged with 215 sacks 60/40 Pozmix, 6% gel, 1/4# Floseal per sk as follows: 50 sx @ 1454', 80 sx @ 670', 50 sacks @ 280', 10 sx @ 40', 15 sx rathole, 10 sx mousehole. P.D. @ 3:00 a.m. 11/20/92.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. of Kansas  
STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Sedgwick, ss. 12-8-92  
DEC 8 1992

John S. Weir (Employee or Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well has been filled that the same are true and correct, so help me God.

(Signature) John S. Weir

(Address) P.O. Box 8647, Wichita, Ks. 67208

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 92



Sheryl L. Murphy  
Sheryl L. Murphy Notary Public