


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Rush County, Sec. 2 Twp. 19S Rge. (E) 20(W)
Location as "NE/CNW/SE" or footage from lines SW SW SE
Lease Owner Palomino Petroleum
Lease Name Bott Well No. 1
Office Address 304 Insurance Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 30 19 75
Application for plugging filed July 30 19 75
Application for plugging approved July 30 19 75
Plugging commenced July 30 19 75
Plugging completed July 30 19 75
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4280 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	306'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: Plugged at 500' with 50 sacks of 50-50 pozmix; plugged at 240' with 25 sacks of 50-50 pozmix; plugged at 40' with 10 sacks of 50-50 pozmix. Plug down at 4:45 A. M. July 30, 1975.

RECEIVED
STATE CORPORATION COMMISSION
AUG 0 1975
8-6-75

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Strata Drilling Company
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Kenneth J. Link

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link
Kenneth J. Link, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 31st day of July, 1975
December 14, 1977
Elaine H. Taylor
Notary Public.



15-165-20542-0000

D R I L L E R S L O G

#1 Bott

CASING RECORD:
300.73' of used 8-5/8"
surface casing.

COMPANY: Strata Drilling Company

DESCRIPTION: SW SW SE
Section 2-19S-20W
Rush County, Kansas

CONTRACTOR: Palomino Petroleum

TOTAL DEPTH:
4280'

COMMENCED: July 22, 1975

COMPLETED: July 30, 1975

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	314	Ran 300.73' of used 8-5/8" surface casing; set and cemented at 306' with 185 sacks of common cement, 2% gel and 3% C. C. Plug down at 7:15 A. M. July 23, 1975.
Shale, Sand & Shale	314	1165	
Sand Streaks & Shale	1165	1510	
Shale & Red Bed	1510	1880	
Shale & Lime	1880	3830	
Lime w/Shale Streaks	3830	3928	
Lime & Shale	3928	4280	

ROTARY TOTAL DEPTH: 4280'

Ran drill stem test.

No electric log.

D. & A.

Hole plugged as follows: Plugged at 500' with 50 sacks of 50-50 pozmix, plugged at 240' with 25 sacks of 50-50 pozmix; plugged at 40' with 10 sacks of 50-50 pozmix. Plug down at 4:45 A. M. July 30, 1975.

8-6-75

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Subscribed and sworn to before me this 31st day of July, 1975.

My Commission Expires:

December 14, 1977

Elaine H. Taylor
Elaine H. Taylor, Notary Public