

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Rush County, Sec. 2 Twp. 19S Rge. (E) 20W(W)

Location as "NE/CNW/SW" or footage from lines NW SW SE  
Lease Owner Pickrell Drilling Company  
Lease Name Bott "A" Well No. 1  
Office Address 705 4th Natl. Bank Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Feb. 1, 19 68  
Application for plugging filed Feb. 1, 19 68  
Application for plugging approved Feb. 5, 19 68  
Plugging commenced Feb. 1, 19 68  
Plugging completed Feb. 1, 19 68  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4294' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	274'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 600'. Set plug. Cemented with 70 sacks of cement.  
Heavy mud to 270'. Set plug. cemented with 20 sacks cement.  
Heavy mud to 40'. Set plug. Cemented to bottom of cellar with  
10 sacks of cement. Plugged rat hole with 2 sackscement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 15 1968  
2-15-68  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 4th Natl Bank Bldg, Wichita, Ks. 67202  
(Address)

Subscribed and sworn to before me this 9th day of February, 19 68



L. M. Whiting  
Notary Public.

My commission expires May 10, 1970

15-165-20108-0000  
**ROTARY DRILLING LOG**

9

**COMPANY:** Pickrell Drilling Company  
705 Fourth National Bank Bldg.  
Wichita, Kansas 67202

Rotary Drilling Commenced 1/22/68

Rotary Drilling Completed 2/1/68

**LOCATION:** Bott "A" No. 1  
NW SW SE Section 2-19S-20W  
Rush County, Kansas

**CONTRACTOR:** **PICKRELL DRILLING COMPANY**  
**Wichita, Kansas**

**CASING RECORD:** (14 jts.) 8 5/8" surface casing set at 274' and cemented with 160 sacks cement. Complete @ 6 PM, January 22, 1968. No oil string was run. D. & A., plugged February 1, 1968.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

80	clay & Post Rock	C. F. S.
130	Shale	4170'
520	Shale & Shells	4174'
535	Blaine	4187'
805	Shale & Shells	4195'
1040	Snad	4204'
1389	Shale & Shells	4225'
1428	Anhydrite	4245'
1805	Shale & Shells	4285'
2180	Shale & Lime Streaks	4294'
2495	Lime & Shale	
2715	Lime	
3765	Lime & Shale	Slope Tests
4000	Lime	3000'
4140	Lime & Shale	3500'
4174	Lime	4000'
4187	Sand	
4225	Sand & Lime	
4235	Lime, Shale & Sand	S. L. M.
4273	Lime & Shale	3995.58'
4294	Mississippian, RTD	Strap Board 3995.21'
		Strap Long .37'

**RECEIVED**  
STATE CORPORATION COMMISSION  
2-15-68  
**FEB 15 1968**  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**

By *C. W. Sebitts*  
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 15th day of February, 19 68, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

*L. M. Whiting*  
Notary Public  
L. M. Whiting