

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Rush County. Sec. 2 Twp. 19S Rge. (E) 20 (W)  
Location as "NE/CNW%SW%" or footage from lines SW SW NW  
Lease Owner Continental Oil Company  
Lease Name J. A. Bott Well No. 1  
Office Address Box 161, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-18 19 60  
Application for plugging filed 1-18 19 60  
Application for plugging approved 1-18 19 60  
Plugging commenced 1-18 19 60  
Plugging completed 1-18- 19 60  
Reason for abandonment of well or producing formation No commercial shows encountered.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas  
Producing formation None Depth to top Bottom Total Depth of Well 4310 Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Cherokee sand	Water	4184	4204	8 5/8"	669'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 600' from surface with Halliburton  
plug at that depth. Spotted 20 sacks of cement  
filling hole to 517'. Mudded up to 240'. Spotted  
20 sacks of cement to 157'. Mudded up to 41' and  
capped with 10 sacks of cement to surface.



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Incorporated  
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
F. L. Dunn (employee of owner) or (XXXXXX) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

ARC

1-18-60

State DWM(3) File

(Signature)

District Superintendent

Box 161, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 19 60

My commission expires 8-1-60

Notary Public.

15-165-00266-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- CONTINENTAL OIL COMPANY  
Farm- Bott No. 1

SEC. 2 T. 19 R. 20  
SW SW NW

Total Depth, 4314'

Comm. 1-4-60

Comp. 1-17-60


Shot or Treated.

Contractor. Leben Drilling, Inc.

Issued. 2-20-60

County Rush

KANSAS



Elevation, 2161 RE

Production. Dry

CASING:  
8 5/8" 669' cem. w/350 sx.

Figures indicate Bottom of Formations.

surface soil & clay	40
sand, shale & shells	380
shale & shells	540
iron	548
shale & lime	660
shale & red bed	725
shale & shells	800
sand	1150
red bed	1365
shale & lime	1420
anhydrite	1465
shale & lime shells	1706
shale	2180
lime	2285
lime & shale	3355
lime	4095
lime & chert	4310 RTD
lime	4314
Total Depth	

TOPS: SCOUT

Heebner	3378
Lansing	3724
Base Kansas City	4018
Ft. Scott	4150
Cherokee Sand	4170
Mississippi	4285