

STATE OF KANSAS
STATE CORPORATION COMMISSION
200, Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,324-0000

LEASE NAME Sharp

WELL NUMBER 8-5A

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 8 TWP. 17 SRGE. 29 (X) or (W)

COUNTY Lane

Date Well Completed 9/4/86

Plugging Commenced 11/9/88

Plugging Completed 11/9/88

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1988
CONSERVATION DIVISION
L.B. Industries, Inc.
LEASE OPERATOR
ADDRESS 370 17th St., Suite 3200, Denver, CO 80202
PHONE# (303) 629-1447 OPERATORS LICENSE NO. 3680

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 3, 1988 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Cherokee Depth to Top 4438' Bottom 4540' T.D. 4645'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Cherokee	Oil	Surface	306	8-5/8"	306	0
		Surface	4645	5-1/2"	4645	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug #1 from PBDT at 4554' to surface with 125 bbls 65-35 Pozmix + 10% gel + 2% Econolite with 500 lb hulls in 15 bbls after first 5 bbls - Down 5-1/2" casing to 1000 psi.

Plug #2 - Down 8-5/8" x 5-1/2" annulus with 3 bbls above cement to 300 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5827

Address Ness City, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L.B. Industries, Inc.

STATE OF Colorado COUNTY OF Denver, ss.

Layle L. Robb (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Layle L. Robb

(Address) 370 17th St., Suite 3200, Denver, CO

SUBSCRIBED AND SWORN TO before me this 20th day of November, 1988

Peggy Steffin
370 17th St., Suite 3200
Denver, CO 80202

Peggy Steffin
Notary Public

My Commission Expires: 7/27/92