

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,373-0001

LEASE NAME Snider "A"

WELL NUMBER 1

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 10 TWP. 17S RGE. 29 ~~XXXX~~(W)

COUNTY Lane

Date Well Completed 4-30-87

Plugging Commenced 4-30-87

Plugging Completed 4-30-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR White & Ellis Drilling, Inc.

ADDRESS 401 E. Douglas - Suite 500, Wichita, KS 67202

PHONE#(316) 263-1102 OPERATORS LICENSE NO. 5420

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? YES

Which KCC Office did you notify? District #1

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation ACO-1 and well log will be filed by Operator.

Depth to Top N/A Bottom T.D. 4595'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	368'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Spotted 50 sx. cement @ 2220' thru drill pipe.

Spotted 80 sx. cement @ 1600' thru drill pipe.

Spotted 50 sx. cement @ 400' thru drill pipe.

Spotted 10 sx. cement @ 40' thru drill pipe. Spotted 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.


Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine

(Address) 401 E. Douglas - Suite 500
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 5th day of May, 19 87

My Commission Expires:



DAVID F. JAMIS
NOTARY PUBLIC
STATE OF KANSAS
My Exp. 6-10-87
05-06-1987
MAY 6 1987
Form CP-4
Revised 07-86
CONSERVATION DIVISION
Wichita, Kans.

NOTICE OF INTENTION TO DRILL

CARD MUST BE RETURNED

(see rules on reverse side)

Starting Date 4 month 1 day 87 year

API Number 15-101-21,373-00002

OPERATOR: License # 5420
 Name White & Ellis Drilling, Inc.
 Address 401 E. Douglas - Suite 500
 City/State/Zip Wichita, KS 67202
 Contact Person Michael L. Considine
 Phone (316) 263-1102

NW NE SE Sec. 10 Twp. 17 S, Rg. 29 East
 2310' Ft. from South Line of Section
 990' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5420
 Name White & Ellis Drilling, Inc.
 City/State Wichita, KS 67202

Nearest lease or unit boundary line 330' feet
 County Lane
 Lease Name Snider "A" Well # 1
 Ground surface elevation 2795' (ext.) feet MSL
 Domestic well within 330 feet: yes X no
 Municipal well within one mile: yes X no
 Depth to bottom of fresh water 200'
 Depth to bottom of usable water 1100' 1350'
 Surface pipe by Alternate: 1-2
 Surface pipe planned to be set 350'
 Conductor pipe required None
 Projected Total Depth 4650' feet
 Formation Mississippian

Well Drilled For: Well Class: Type Equipment:
 X Oil SWD X Infield X Mud Rotary
 Gas Inj Pool Ext Air Rotary
 OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
 Operator
 Well Name
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., and eventually plugging hole to KCC specifications.
 Date 3-19-87 Signature of Operator Mark Mielke Title Geologist

For KCC Use:
 Conductor Pipe Required feet: Minimum Surface Pipe Required 225 feet per Alt.
 This Authorization Expires 9-19-87 Approved By 3-19-87
 4-23-87 S.P. - 365'

NW NE SE Sec. 10 Twp. 17 S, Rg. 29 East
 West

PLUGGING PROPOSAL IF ABOVE IS D & A


This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2200'	feet depth with 50	sxs of 60-40 pozmix 2% Gel 3% CC
2nd plug @ 970'	feet depth with 50	sxs of same as above
3rd plug @ 400'	feet depth with 50	sxs of same as above
4th plug @ 140'	feet depth with 10	sxs of same as above
5th plug @	feet depth with	sxs of
(2) Rathole with 10'	sxs	(b) Mousehole with sxs

PUSHER Bob Casper
 TD 4595' FORMATION Miss
 SURFACE PIPE 8 5/8" @ 368'
 ANHYDRITE 2209'-2230' ELEVATION 2795' est.
 STARTING TIME & DATE 2:30 PM 4-30-87
 COMPLETION TIME & DATE 10:15 PM
 1st PLUG @ 2220' FT. WI 50 SX
 2nd PLUG @ 1600 FT. WI 80 SX
 3rd PLUG @ 400 FT. WI 50 SX
 4th PLUG @ 40 FT. WI 10 SX
 60/40 Pozmix
 RAT HOLE CIRCULATED WI 15 SX
 MOUSE HOLE CIRCULATED WI SX
 WATER WELL PLUGGED WI SX
 CEMENT COMPANY Allied
 TECHNICIAN Dan Goodrow, SuwAll

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 6 1987
 05-06-1987
 CONSERVATION DIVISION
 Wichita, Kansas

sho
 8
 052/16



15:101-2/373-0000

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: White & Ellis Drilling, Inc., 401 E. Douglas - Suite 500, Wichita, KS 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Snider "A" Well No. 1

Sec. 10 T. 17 South R. 29 West Spot NW NE SE

County Lane State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 368' with 220 sx. 3% CC 2% Gel

Production: @ with sx.

Type Well: D & A Total Depth 4595'

Drilling Commenced 4-23-87 Drilling Completed 4-30-87

Formation	From	To	Tops
Cellar	0	7	Anhydrite - 2217'
Shale, Lime	7	2210	
Shale, Shells	2210	3260	
Shale, Lime	3260	4335	
Lime	4335	4595	

RECEIVED
STATE COMMISSION COMM. INC.
05-06-1987
MAY 6 1987

Oil & Gas Division
Wichita, Kansas