

15-169-00539-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Melland Drilling Co., Inc.

Complete Address 1111 N. Main, Hutchinson, Kansas 67501

Lease Name Millison Well No. 1

Location SW SW SE Sec. 28 Twp. 16 Rge. 1 (E) (W) X

County Saline Total Depth 2607'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling Company

Address 2809 King, Hutchinson, Kansas License No. 440

Operation Completed: Hour Noon Day 10 Month November Year 1970

The above well was plugged as follows:

Hole filled with sand to 1980' and cemented with 5 sacks cement.

Hole filled with mud to 147'. Rock bridge set from 147' to 140' and hole cemented

with 20 sacks cement. Hole filled with mud to 40'. rock bridge set from 40' to

30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Arthur J. Jordan*
Well Plugging Supervisor

DATE 11-18-70

INV. NO. 2880-W