

[Handwritten mark]

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Melland Drilling Co.
Complete Address 901 North Main, McPherson, Kansas 67460
Lease Name Henry Karber Well No. 1
Location SW NE SW Sec. 28 Twp. 16S Rge. 1 (E) (W)
County Salina Total Depth 2609'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Art Lamb
Address Hutchinson, Kansas License No. 440
Operation Completed: Hour 2 PM Day 7 Month 10 Year 71

The above well was plugged as follows:

8 5/8"-130'-Circulated w/cement. 5 1/2"-2609'-Cemented, Perf. 2050'.
Sand hole to 2000'. 5 Sax.cement 2000' to 1950'. Mud 1950' to 150'.
Bridge 150' to 140'. 25 Sax.cement 140' to 70'. Mud 70' to 40'.
Bridge 40' to 30'. 10 Sax.cement 30' to 0. Pulled 1727'-5 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 10-18-71
INV. NO. 4482-47