



15-169-00752-0000

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

November 7, 1963

RECEIVED  
STATE CORPORATION COMMISSION

NOV 13 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Makely of Melland Drilling Co., Inc this  
 date requested permission to plug the following described well:

Mr. Makely guarantees payment of the plugging fee.

Operator's full Name: F. S. Williams

Complete Address: Box 746, Mc Pherson, Kansas

Lease Name: Mike Karber Well No. 1

Location: SW SW NW Sec. 28 Twp. 16 Rge. 1 ( W)  X

County Saline Total Depth 2642' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Makely was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 135'. Push  
plug and 1/4 sack hulls to 135' and cement with 20 sacks  
through drill pipe. Fill hole with mud to 40'. Push  
plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

  
 Conservation Division Agent