

State of Kansas



15:10:70090.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1974
05-20-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Oden of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Oden guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company

Complete Address: 1130 KSB&T Building, Wichita, Kansas.

Lease Name: Cronic Well No. 1

Location: NW-NW-NE Sec. 30 Twp. 17 Rge. (E)(W) 29

County: Lane Total Depth 4620 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oden was instructed to plug the well as follows:

308'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1210' and displace 110 Cu. Ft. cement thru DP. Pull DP to 315' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent