



CP2

15:169:00578:0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

March 25, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Knight Casing Pulling Co., Inc.

Complete Address: Box 405, Chase, Kansas 67524

Lease Name: Threlkeld Well No. 1

Location: C NE SE Sec. 19 Twp. 16 Rge. 1 (S) (W) X

County: Saline Total Depth 2698' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:


Fill hole with sand to 2670' and cement with 6 sacks cement.

Fill hole with mud to 140'. Set rock bridge from 140' to 130' and

cement hole with 30 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 15 sacks cement.

Very truly yours,


Conservation Division Agent