



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

1 May 1982

RECEIVED  
STATE CORPORATION COMMISSION  
MAY - 6 1982  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)  
15-101-20,657-0600

Dear Sir:

Mr. Jim Loftis of Slawson Drilling Co. <sup>Inc.</sup> has this  
date requested permission to plug the following described well:

Operator's Full Name Donald C. Slawson & American Energies

Complete Address: 200 Douglas Bldg. Wichita, Kansas 67202

Lease Name: Zink Well No. D1

Location: C-NE-SW-SE Sec.      Twp.      Rge.      (E) (W)     

County: Lane Total Depth: 4630'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A     

Other well as hereafter indicated:     

Mr. Loftis was instructed to plug the well as follows:

They cement circulated 461' of 8 1/8" surface casing with 325 lbs  
of cement. The Dakota was topped at 1292' the anhydrite was  
toped at 2219'. 1st plug at 2200' with 65 lbs of cement &  
2nd plug at 1380' with 65 lbs of cement. 3rd plug at 480'  
with 35 lbs of cement. 4th plug at 40' to 0' on solid bridge  
with 10 lbs of cement. Then circulated 10 lbs of cement in  
(Over) Very truly yours,

Paul A. Luthi  
Conservation Division Agent