

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15-101-19034-0001

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 7 1965  
07-07-1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bob Sargent of Sargents Casing Pulling has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Oil and Gas Property Management,

Complete Address: 6th Floor C & I Life Building, Houston, Texas.

Lease Name: Boomhower Well No. 1

Location: CNE-SE Sec. 16 Twp. 17 Rge. (E) (W) 29

County Lane Total Depth 2900 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

265'--8 5/8" Surface pipe, cement circulated.  
2829'--4 1/2" Production casing cemented with 200 Sx. Top of cement @ 2614'. Top perforations @ 2772'.

Squeeze bottom of hole with 10 Sx. cement leave top of cement @ 27.00. Pull 4 1/2" to 660' and circulate heavy gel mud. Pull 4 1/2" to 600' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 240' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2", set rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. A. Nichols  
Conservation Division Agent