

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 5 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Kevert of Birmingham-Bartlett Drlg. has this date requested permission to plug the following described well:

Mr. Kevert guarantees payment of the plugging fee.

Operator's full Name: Birmingham-Bartlett Drlg. Co.

Complete Address: 300 Kaufman Bldg., Wichita, Ks.

Lease Name: Abele Well No. 2

Location: NW SE NW Sec. 4 Twp. 18 Rge. 18 (E)(W) XX

County: Rush Total Depth 3958' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Kevert was instructed to plug the well as follows:
 Gun pits, circulate heavy mud, set cementing plug at 500' and displace
25 sk cement thru drill pipe. Heavy mud to, 40' set cementing plug, 1/2 sk
hulls and 10 sk cement to base of cellar. Plug rat hole with 2 sk cement.

Very truly yours,

Les J. Messer
 Conservation Division Agent