

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 24 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ogle of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Donald C. Sl wson

Complete Address: 408 One Twenty Bldg., Wichita, Ks.

Lease Name: Oborny "A" Well No. 1

Location: NW NW SW Sec. 13 Twp. 18 Rge. 18 (E)(W) X

County: Rush Total Depth 3769 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and displace
25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2
sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc
cement.

Very truly yours,

Geo. F. Mansour
 Conservation Division Agent