

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

7-17-98

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-101-21562-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR LANDMARK OIL Exploration KCC LICENSE # 06113
(owner/company name) (operator's)

ADDRESS 1816 N. Rock Rd. STE 205 CITY Wichita

STATE KANSAS ZIP CODE 67206 CONTACT PHONE # (316) 683-8080

LEASE PELTON 1 WELL# 1-25 SEC. 25 T. 17-S R. 29 (East/West)

NE SE NW SPOT LOCATION/0000 COUNTY LANE

3630 FEET (in exact footage) FROM (S) (circle one) LINE OF SECTION (NOT Lease Line)

2970 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 7/8 SET AT 302 CEMENTED WITH 180 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 4595 CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4153-4157-4557-54 4546-48

ELEVATION 2783 T.D. 4597 PETD 4595 ANHYDRITE DEPTH 2163
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLOGGING 35 sks + 102 lbs Hulla port collar @ 2153

135 sks gel spacer to 2163' cement to surface w/ 165 sks max # 500 shut-in off 325 sks cement

2 1/2 bbl pumped surface casing held 300#/Found cement top @ 350' - fill csq w/ 25 sks cement &
(If additional space is needed attach separate page) cut off head

witnessed by Kevin Strube
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? _____

If not explain why? will be mailed from office

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

ALLAN Walker PHONE# (316) 792-3336

ADDRESS 2535 21st City/State Great Bend, ks

PLUGGING CONTRACTOR Allied Cementing KCC LICENSE # _____
(company name) (contractor's)

ADDRESS _____ PHONE # () _____

PROPOSED DATE AND HOUR OF PLOGGING (If Known?) 3-11-98 9:00 AM

PAYMENT OF THE PLUGGING FEE (K.S.A. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-13-98 AUTHORIZED OPERATOR/AGENT: Allan Walker
(signature)