

1 030785

MAR 1 1 1987 15-165-21311-0000

134

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completion date 8/26/85

SE SW SE, SEC. 8, T 18 S, R 18 W/E
330 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Morse Well # 1

Operator: Frontier Oil Company

County Rush 130.00

Name & Address 1720 KS State Bank Bldg.

Well Total Depth 4000 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 600

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 11 Month: 3 Year: 19 87

Plugging proposal received from Dick Parker

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: 4 1/2" at 3950' PRTD 3860' Perfs at 3841-44' Elevation 2090' Anhydrite 1250'

1st plug sand back to 3790' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 1250',

3rd plug pump 75 sx cement at 700',

4th plug pump 10 sx cement at 50-0',

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 5:30 p.m. Day: 11 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sand back to 3790' and dumped 4 sx cement on top of sand
through bailer,

(spotted through 4 1/2" casing) 2nd plug at 1250' with 50 sx cement,

3rd plug at 700' with 75 sx cement,

4th plug at 50-0' with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Recovered 2200' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)INVOICED
I hereby certify that I have observed this plugging.

DATE 3-27-87

INV. NO. 16445

Signed Steve Durrant
(TECHNICIAN)3-26-87
MAR 26 1987FORM CP-2/3
Rev. 01-84

GREAT GUNS

Gamma Ray
Neutron

FILING NO.

COMPANY Frontier Oil Co.WELL Morse No. 1

FIELD _____

COUNTY RushSTATE KansasLocation: SE - SW - SE

Other Services:

Sec. 8 Twp. 18ⁿ Rge. 18^wPermanent Datum Ground LevelElev. 2090Elev.: K.B. 2095Log Measured From Kelly Bushing, 5 Ft. Above Perm. DatumD.F. -Drilling Measured From Kelly BushingG.L. 2090

Date

8-26-85

Run No.

oneoneone

Type Log

Gamma RayCCLNeutron

Depth—Driller

400040004000

Depth—Logger

389738973897

Bottom Logged Interval

38883892.53896

Top Logged Interval

310031003100

Type Fluid in Hole

dryGravity API

Density

Level

dry

Max Rec Temp Deg F

Operating Pressure

Equip No. & Location

1 in.40 Hays

Recorded By

D. Yunker

Witnessed By

T. PischerFIELD
PRINT

BORE-HOLE RECORD				CASING RECORD			
Run	No.	Bit	From	No.	Bit	From	To
one	12 1/4	00	600	8 1/8	24	00	600
two	7 7/8	600	4000	4 1/2	10.5	00	3950

STATE CORPORATION COMMISSION

FEB 23 1987

2-23-87
CONSERVATION DIVISION
Wichita, Kansas