

To: 1 050676
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,318-~~0000~~
SESWW, SEC. 13, T 18 S, R 18 W
330 feet from S section line

TECHNICIAN'S PLUGGING REPORT

4290 feet from E section line

Operator License # 5027

Lease Name "J." Oborny Well # 1

Operator: J. A. Allison
Name & Address: 300 West Douglas
Suite 305
Wichita, Kansas 67202

County Rush 123.27
Well Total Depth 3793 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1150

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Woodmen - Tanitti Drilling License Number 5122
Address 704 Union Center Bldg. Wichita KS 67202

Company to plug at: Hour: 6:00 Day: 28 Month: ~~November~~ October Year: 19 85

Plugging proposal received from Elmer Zimmerman

(company name) Woodman - Tanitti Drilling (phone) 316-265-7650

Work: Keep hole full of heavy mud & spot cement
plugs through drill pipe. 1st plug @ Base of
the surface pipe with 50sx. 2nd plug @ 550' with
50sx. 3rd plug @ 40' with a solid bridge plug and
10sx of cement circulate 15sx in the rathole.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 7:30 pm Day: 28 pm Month: October Year: 19 85

ACTUAL PLUGGING REPORT kept hole full of heavy mud & spotted
cement plug through drill pipe. 1st plug @ 1190' w/50sx
2nd plug @ 550' w/40sx
3rd plug @ 40' w/SBP+10sx
Circulate 15sx in the rathole

Anhydrite @ 1150 Elevation 2005

Remarks: Allied cementing pumped 60/40 poz. 6% gel cement
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 22 1985

INV. NO. 11101

RECEIVED
STATE CORPORATION COMMISSION
11-18-85
NOV 18 1985

Signed Richard W. Lacey
(TECHNICIAN)