

6 040812

10-29-87

API NUMBER 15-051-23887-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW NE, SEC. 36, T 11 S, R 19 W/E

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8925

Lease Name Johnson Well # 4

Operator: Liberty Operations and Comp. Inc.

County Ellis 121.71

Name & Address: 308 West Mill

Well Total Depth 3745 feet

Plainville, Kansas 67663

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 210 cwc

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Russell, Kansas

Company to plug at: Hour: 10:00 AM Day: 29 Month: October Year: 19 87

Plugging proposal received from Roger Comeau

(company name) Liberty Operations and Comp. (phone) _____

were: 4 1/2" casing set at 3663'. w/150 sks cement.

Perf at 3363' - 3514. Anhy 1400' cemented w/340 sks.

Holes in casing at 850' and 1080'

Ordered 150 sks 65/35 Poz 10% Gel 2% Lite w/1/4# Flocele plus 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1:00PM Day: 29 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT

Hooked up 4 1/2" casing. Pdmped in 150 sks 65/35 Poz 10% Gel w/1/4# Flocele plus 5 sks Hulls. Max 700# S.I. 400# 8 5/8" S.P. Cement to surface.

RECEIVED STATE CORPORATION COMMISSION

NOV 30 1987

CONSERVATION DIVISION Wichita, Kansas

Remarks: _____ (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-4-87

Signed Dennis L. Hamel (TECHNICIAN)

INV. NO. 19124

Dennis L. Hamel

10-29

INVOICE

December 4, 1987 19

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

To: Liberty Operations & Comp. Inc.
308 West Mill
Plainville, Kansas 67663

200 COLORADO DERBY BLDG., 202 W. 1st ST.
WICHITA, KANSAS 67202-1202

FOR: Plugging ASSESSMENT AS FOLLOWS:

INVOICE No.: 19124 API#NA

Johnson #4
SE NW NE
Sec. 36-11S-19W
Ellis County
3745' \$121.71
Allied Cementing Co.

NOTE: We still need a Well Plugging Record (CP-4) on this well.

PAYABLE UPON RECEIPT

TO INSURE CORRECT APPLICATION KINDLY
RETURN PINK COPY WITH REMITTANCE

CD