

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-22,676-0000

SE-NW-SW, Sec. 26, T 11 S, R 19 W E

1650 feet from N S section line

990 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8925

Lease Name JOHNSON Well #B-1

Operator: LIBERTY OPERATIONS +
Name & ADDRESS COMPLETIONS

County ELLIS

308 WEST MILL
PLAINVILLE, KANSAS
67663

Well Total Depth 3709 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 277

120.54

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor PIONEER DRILLING CO License Number 5665

Address 308 WEST MILL, PLAINVILLE, MO. 67663

Company to plug at: Hour: 5:00 AM Day: 3RD Month: NOV. Year: 19 83

RECOMMENDATIONS
VERBAL PLUGGING ORDERS GIVEN TO DON HAMBURSTER

(company name) PIONEER DRILLING CO. (phone) 913-434-4686

were: 8 5/8" 277 FT SR. CUL 175 SK CO 140 FORMIX x 2% GEL 3% CA-CL. (ALLEN)

ORDER 200 SK 50/50 FORMIX 4% GEL 3% CA-CL. AND 8 5/8" PLUG
SPOT WITH DRILL STEM-TURN HOLE OVER, HEAVY MUD BETWEEN PLUGS
RIGBUCKLE 3685, ELV 2061, ANH. 1480 FT

Signed Marion Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:38 AM Day: 3RD Month: NOV. Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 200 SK 50/50 FORMIX 4% GEL-3% CA-CL. 9 8 5/8" Plug
SPOTTED WITH DRILL STEM, TURNED HOLE OVER, HEAVY MUD BETWEEN PLUGS
1st Plug @ 3660 FT 20 SK CNT., 2nd Plug @ 1410 20 SK CNT
3rd Plug @ 420 FT 100 SK CNT 1 SK CALLO-FLAME 4th Plug @ 370 40 SK CNT.
5th Plug SOLID BRIDGE HULLS-PLUG @ 40 FT 0 10 SK CNT., 10 SK RAT HOLE (AIR)

Remarks: CEMENTED BY ALLEN QNT

I hereby certify that the above plugging instructions were given as herein stated
and that I ~~did~~ / did not) observe this plugging.

DATED 11-21-83
INV. NO. 7012-W

RECEIVED
STATE CORPORATION COMMISSION

NOV 10 1983

CONSERVATION DIVISION
Wichita, Kansas

Signed Marion Schmidt
(TECHNICIAN)