

5 020281

169-00535-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 3-20-53

~~SW NE 1/4~~ SEC. 20, T. 16 S, R. 1 (W/E)

4290 feet from N(S) section line

990 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Tressin B Well # 1

Operator: Phillips Petroleum Company

County Saline 86.22

Name & Address Rt. #3, Box 20-A, Great Bend, KS

Well Total Depth 2653 feet

67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 131'-10056

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Great Bend, Kansas

Company to plug at: Hour: 10:00 AM Day: 26 Month: March Year: 19 86

Plugging proposal received from Fred Smith

(company name) Phillips Petroleum Company (phone) 316 793 8421

were: Pump 25 sacks 60/40 Pozmix w/6% gel, 10 sacks Bentonite, 3 sacks hulls, and 100 sacks 60/40 Pozmix w/6% gel into 7" casing.

Pump 100 sacks 60/40 Pozmix w/6% gel into 10 3/4"-7" annulus.

RECEIVED

STATE CORPORATION COMMISSION

Plugging Proposal Received by [Signature]

APR 7 1986

(TECHNICIAN)

CONSERVATION DIVISION Operations attended by Agent?: All Part _____ None _____

Wichita, Kansas

Operations Completed: Hour: 11:50 AM Day: 26 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 25 sacks 60/40 Pozmix w/6% gel, 10 sacks Bentonite, 3 sacks hulls, and 100 sacks 60/40 Pozmix w/6% gel pumped into 7" casing. 100 sacks 60/40 Pozmix w/6% gel pumped into 10 3/4"-7" annulus.

No casing recovery.

7" 2645-150 gks PerFS 1859-63' Max Press 500 PSIG - Close in 300 PSIG (7")

Remarks: Max Press 250 PSIG - 100 PSIG close in (10 3/4") B. J. Titan # 279572

(If additional description is necessary, use BACK of this form.)

INVOICED

(client did not) observe this plugging.

DATE 4-8-86

Signed [Signature] (TECHNICIAN)

INV. NO. 13347

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER _____ (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Phillips Petroleum Company OPERATORS LICENSE NO. 5229

ADDRESS Rt. #3, Box 20-A, Great Bend, Kansas 67530 PHONE # (316) 793-8421

LEASE (FARM) Tressin "B" WELL NO. 1 WELL LOCATION S/4 NE NE COUNTY Saline

SEC. 20 TWP. 16S RGE. 1W ~~16E~~ (W) TOTAL DEPTH 2653' PLUG BACK TO 1876'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 10 3/4" SET AT 131' CEMENTED WITH 100 SACKS

CASING SIZE 7" SET AT 2645' CEMENTED WITH 150 SACKS

PERFORATED AT 1859-63'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump down casing with 25 sx 60-40 Pozmix with 6% gel, 10 sx gel containing 3 sx hulls and 100 sx 60-40 Pozmix with 6% gel. Tie onto bradenhead and pump 100 sx 60-40 Pozmix with 6% gel into 10 3/4" - 7" annulus.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACC-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN April 15, 1986

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES & REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

G. L. Kelso

PHONE # (316) 793-8421

ADDRESS Rt. #3, Box 20-A, Great Bend, Kansas 67530

PLUGGING CONTRACTOR N.A.

LICENSE NO. _____

ADDRESS _____

PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR AGENT RECEIVED KCC-KDHE

SIGNED: _____

Kane A. Kestly
(Operator or Agent)

MAR 17 1986

DATE: _____

3-11-86

JOINT OFFICE #5
Salina, KS