

9-18

2-060278

214  
R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-169-20,285-0000

165' S NW NE SE, SECTION 20 TOWNSHIP 16 RANGE 1W

OPERATOR LICENSE # 30111 2310 FEET FROM S SECTION LINE  
990 FEET FROM E SECTION LINE

OPERATOR K. C. Development, Inc.  
NAME & RR #1, Box 56  
ADDRESS Florence, KS 66851

LEASE NAME: Redden #1

COUNTY: Saline 61.45

WELL TOTAL DEPTH: 1891'

PIPE: 5-1/2" @ 1891'

SURFACE CASING: 8-5/8" @ 200'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SMD  D&A   
OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: K. C. Development  
ADDRESS: RR #1, Box 56, Florence, KS 66851 LICENSE: 30111

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ pm DAY: 18 MONTH: 9 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Rex Savage  
COMPANY NAME: K. C. Development PHONE: 316-382-3540

WERE: Spot 10 sx cmt thru tub from 1840'-1740' - shoot pipe  
& pull - bridge set @ 260' - slurry cmt to surface.

PLUGGING PROPOSAL RECEIVED BY: Dist #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 4:00p DAY: 18 MONTH: 9 YEAR: 1991

ACTUAL PLUGGING REPORT:  
Spotted 10 sx cmt thru tub from 1840' - 1740' - shot  
pipe & pulled - set solid bridge from 260-250' - had to  
add water 280'-260' - slurry cmt from 250' to surf.  
The mix was 50 sx cmt, 725 gal wtr, 3 sx gel, no sand

REMARKS: Concrete Products #17338 - recovered 1540'

I DID OBSERVE THIS PLUGGING

RECEIVED

KANSAS CORPORATION COMMISSION

R. Phil Worley  
R. Phil Worley (AGENT)

INVOICED

DATE 10-18-91 OCT 2 1991

INV. NO. 32389  
CONSERVATION DIVISION  
WICHITA, KS

FORM CP-2/3  
REV. 3/90