

1 020050

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,371-0000

SE NE NE, SEC. 9, T 18 S, R 18 W/E

4290 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Lease Name Zetko Well # 1

Operator: J.A. Allison

County Rush 124.96

Name & Address 300 West Douglas, Suite 305

Well Total Depth 3845 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1258

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Woodman-Iannitti Drilling Co. License Number 5122

Address 805 Union Center Bldg., Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 13 Month: 1 Year: 19 87

Plugging proposal received from Rich Wheeler

(company name) Woodman-Iannitti Drilling Company (phone) 316-587-3477

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1290' with 50 sx cement, 2nd plug at 500' with 40 sx cement,

3rd plug at 40-0' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement.

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:30 a.m. Day: 14 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1290' with 50 sx cement,

2nd plug at 500' with 40 sx cement,

3rd plug at 0-40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

Inspector (if not) observe this plugging.

STATE CORPORATION COMMISSION

1-15-87
JAN 15 1987

CONSERVATION DIVISION
Wichita, Kansas

Signed Glenn R. Barlow
(TECHNICIAN)

INVOICED

DATE 1-16-87

WV. NO. 15927

1-14

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date January 9 1987

API Number 15-165-21,371-0000

OPERATOR: License # 5027
Name J. A. Allison
Address 300 West Douglas, Suite 305
City/State/Zip Wichita, Kansas 67202
Contact Person J. A. Allison
Phone 316-263-2241

SE NE NE Sec. 9 Twp. 18 S, Rg. 18W
4290 Ft. from South Line of Section
330 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County RUSH

CONTRACTOR: License # 5122
Name Woodman-Iannitti Drilling Co.
City/State Wichita, Kansas 67202

Lease Name ZETKO Well # 1
Ground surface elevation 2060 feet MSL

Well Drilled For: Well Class: Type Equipment:
Oil SWD Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 250-285
Depth to bottom of usable water 450

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 1250

Conductor pipe required none
Projected Total Depth 3820 feet

Formation Arbuckle

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date Dec 31, 1986 Signature of Operator or Agent J. A. Allison Title Operator

For KCC Use:

Conductor Pipe Required 7-2-87 feet; Minimum Surface Pipe Required 450 feet per Alt. 1 X

This Authorization Expires 7-2-87 Approved By Rch 1-2-87

more in set ground 1200ft at set 1255 of 898

SE. NE. NE Sec. 9 Twp. 18 S, Rg. 16 West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug description, feet depth, feet depth, and sxs of cement. Includes entries for 1st, 2nd, 3rd, 4th, and 5th plugs, and Rathole/Mousehole.

Log table with columns: Pusher, TD, Surface Pipe, Anhydrite, Starting Time & Date, Completion Time & Date, 1st-4th Plug, Rat Hole Circulated, Mouse Hole Circulated, Water Well Plugged, Cement Comp, Technician. Includes handwritten notes and a date stamp 1-15-87.