

To: 1 070888  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-3  
API NUMBER 13- 165-21,298-0000  
50' E of  
SE SW SE, SEC. 9, T. 18 S, R. 18 W/E  
330 feet from S section line  
1600 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5027

Lease Name Young Well # 3  
County Rush 124.86  
Well Total Depth 3842 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1265

Operator: J.A. Allison  
Name & Address 300 W. Douglas, Suite 305  
Wichita, KS 67202

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:40 p.m. Day: 3 Month: 12 Year: 19 90

Plugging proposal received from Millard Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3840' w/100 sx cement, Open hole at 3840-42'  
1st plug sand back to 3790' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 1 sx hull, 10 sx gel, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 3 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3790' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
12-10-90  
DEC 10 1990

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500 lbs of 5 1/2" casing.  
(If additional description is necessary, use BACK form.)

**INVOICED**  
(If additional description is necessary, use BACK form.) observe this plugging.

DATE 1-7-91

Signed Dan Goehm  
(TECHNICIAN)

INV. NO. 30361