

1031391

007-20756-00-00
API NUMBER 15-~~007-20751~~ KCC-CS-8-31-13

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

N/2 NW SE, SEC. 33, T 30 S, R 11 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 7963

4-8
Rec'd
04-11-1994

2045 feet from S section line

1980 feet from E section line

Lease Name Cargill Well # 33-10

Operator: Fancher Oil Company

County Barber

Name & Address 1801 Broadway, Trinity Pl., Ste. 720

Well Total Depth 3900 126.75 feet

Denver, CO 80202-3835

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 236

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS, 67104

Company to plug at: Hour: 11:30 a.m. Day: 8 Month: 4 Year: 19 96

Plugging proposal received from Bill Musgrove

(company name) Bowers Drilling (phone) 316-886-5520

logs: 4 1/2" at 3893' w/100 sx cement, PBSD 3853', Perfs at 3750-53, 3834-37'

1st plug squeeze with 30 sx cement on bottom,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:05 p. Day: 8 Month: 4 Year: 1996

ACTUAL PLUGGING REPORT 1st plug squeezed with 30 sx cement. Maximum pressure 2000 psi.

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2720' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (if desired) observe this plugging.

APR 18 1996

Signed Steve Durrant (TECHNICIAN)

DATE

INV. NO. 45342