

To: 1041130.
STATE CORPORATION COMMISSION 12-12
Wichita State Office Bldg. **PLUGGING SECTION**
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-20,602-00-00
NW SE NE, SEC. 33, T 30 S, R 11 W/E
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7963

Operator: Fancher Oil
Name & Address Trinity Place
1801 Broadway #720
Denver, CO 80202

Lease Name Keimig Well # 33-8

County Barber

Well Total Depth 3880 ^{126.10} feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 204

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 12 Month: 12 Year: 19 95

Plugging proposal received from Darrell Musgrove

(company name) Bowers Drilling (phone) 316-886-5520

Work: 4 1/2" at 3878' w/100 sx cement, PBSD 3853', Perfs at 3731-34, 3750-54'

1st plug sand back to 3680' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 p.m. Day: 12 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3680' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 400 psi.

Remarks: Used 65/35 Pozmix 6% gel by Allied. Recovered 2267' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE 1-8-96
INV. NO. 44439

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1995
CONSERVATION DIVISION
Wichita, Kansas