

1041131

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-007-20,583-00-00

NW NW NW, SEC. 34, T. 30 S, R. 11 W/K

4950 feet from S section line

4950 feet from E section line

Lease Name Keimig Well # 34-4

County Barber

Well Total Depth 4525 147.06 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 12 Month: 12 Year: 19 95

Plugging proposal received from Darrell Musgrove

(company name) Bowers Drilling (phone) 316-886-5520

were: 4 1/2" at 3908' w/100 sx cement, PBSD 3858', Perfs at 3751-53'

1st plug sand back to 3700' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 12 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3700' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pump 100 sx cement.

Maximum pressure 800 psi and shut in 400 psi.

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1995
12-14-1995
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 65/35 Pozmix 6% gel by Allied. Recovered 3052' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Steve J. Pfeifer
(TECHNICIAN)

DATE 1-8-96

INV. NO. 44441