

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22745-00-00
Spot: NWNW Sec/Twnshp/Rge: 26-30S-11W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: MEASE Well Number: 1
County: BARBER Total Vertical Depth: 3900 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

Production Casing Size: 4.5 feet: 3891 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 264 WITH 200 SX CMT

126 75

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/07/2003 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3650' & 4 SX CMT. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/07/2003 2:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 3740'. PERFS AT 3700-3705'. SANDED TO 3650' & 4 SX CMT. 1ST PLUG AT 700' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
OCT 15 2003
KCC WICHITA
10-15-2003

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2850' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 10-15-03

REV. NO. 2004061635

Form *2123*