

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21193-00-01
Spot: NWSWNW Sec/Twnshp/Rge: 18-18S-27W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: BORRELL Well Number: 1-18
County: LANE Total Vertical Depth: 4660 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 4372 WITH 100 SX CMT
Surface Casing Size: 8.625 feet: 303 WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/01/2003 1:10 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: TED FUCHS Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP DOWN 5 1/2" CASING WITH 300# HULLS & 382 SX CMT. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS WITH 50 SX CMT. CUT OFF CASING STRINGS BELOW PLOW DEPTH & RESTORE LOCATION.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/01/2003 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PBTD 4372'. PERFS AT 4254-4256'. DV TOOL @ 2100'. CEMENTED WITH 400 SX CMT. CMT CIRCULATED TO SURFACE. PUMP 300# HULLS & 60 SX CMT FOR BOTTOM PLUG. PUMPED 330 SX CMT. PRESSURED TO 400#. SHUT IN WITH 400#. COULD NOT TIE ONTO BACKSIDE. THE HEAD WAS CEMENTED UP PAST THE TWO INCH OPENINGS.

RECEIVED
7-16-03
JUL 16 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 0



Signed

Michael Maier
(TECHNICIAN)

Form CP-2/3