

3-17

129 R

1 110133

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,504-0000  
SE SE SW, SEC. 9, T 18 S, R 27 W/E  
330 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5104  
Operator: Blue Goose Drilling Co., Inc.  
Name & Address P.O. Box 1413  
Great Bend, KS 67530

Lease Name Borell C Well # 1  
County Lane 150.57  
Well Total Depth 4633 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104

Address P.O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 5 a.m. Day: 17 Month: 3 Year: 19 89

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Company, Inc. (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2697'  
Anhydrite 2060-92'

1st plug at 2092' with 40 sx cement, 2nd plug at 1300' with 90 sx cement,

3rd plug at 230' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by James R. Kapp  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:30 a.m. Day: 17 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2092' with 40 sx cement,

2nd plug at 1300' with 90 sx cement,

3rd plug at 230' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1989  
3-23-89  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 3-27-89 (do not observe this plugging.)

Signed James R. Kapp  
(TECHNICIAN)

INV. NO. 24223  
3-17 MAY 16 1989