

1 030592

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,253-*cal*

S/2 SE NE, SEC. 9, T 18 S, R 27 W/EX

2970 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5693

Lease Name Borell Well # 1

Operator: W. L. Hartman Trust

County Lane 152.75

Name & Address P. O. Box 54

Well Total Depth 4700 Mississippi feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling Co., Inc. License Number 5104

Address P. O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 9:45 am Day: 1 Month: December Year: 1985

Plugging proposal received from LeRoy Borron

(company name) Blue Goose (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2676'
Anhydrite 1060-93'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 75 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:15 pm Day: 1 Month: December Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1100' with 70

sx cement, 3rd plug at 260' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 16 1985

INV. NO. 11509

observe this plugging. STATE CORPORATION COMMISSION signed

DEC 5 1985
12-5-85
CONSERVATION DIVISION

Steve Dumont
(TECHNICIAN)