

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21749-00-00
Spot: S2NWNE Sec/Twnshp/Rge: 22-18S-18W
990 feet from N Section Line, 2030 feet from E Section Line
Lease/Unit Name: TOMECEK Well Number: 22-1
County: RUSH Total Vertical Depth: 3824 feet

Operator License No.: 3869
Op Name: IMPERIAL OIL PROPERTIES, INC.
Address: 200 E FIRST ST., SUITE #413
WICHITA, KS 67202

Surface Casing Size: 8.625 feet: 1234

\$124.25

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/06/2003 12:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: RICH WHEELER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1240' WITH 40 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 05/06/2003 3:00 PM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: MICHAEL MAIER

Actual Plugging Report:


1ST PLUG AT 1240' WITH 40 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

RECEIVED
MAY 23 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY HALLIBURTON.

Plugged through: DP

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED

5-29-03

2003061587

Form CP-23