

1 030500

*R*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-21.308-0000  
NE NW SE, SEC. 22, T 18 S, R 18 W/X  
2310 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Lease Name Keener Well # 4

Operator: J. A. Allison  
Name & Address 300 West Douglas, Suite 305  
Wichita, KS 67202

County Rush 123.47  
Well Total Depth 3799 Arbuckle 5' feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1173

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Woodman-Iannitti Drilling Co. License Number 5122

Address 704 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 31 Month: August Year: 19 85

Plugging proposal received from Elmer Zimmerman

(company name) Woodman-Iannitti (phone) 316-265-7650  
Elevation 2016'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1188'

1st plug 50' into the Arbuckle if necessary with 40 sx cement

2nd plug 30' below the base of the surface pipe with 40 sx cement

3rd plug at 600' with 25 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement  
Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:30 am Day: 31 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1205' with 40 sx cement, 2nd plug at 600' with 25 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement. 5th plug to circulate rat hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 6 1985

7-6-85  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

(If not) observe this plugging.

INVOICED

DATE SEP 10 1985

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 9906