

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barber County. Sec. 36 Twp. 30 Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Schafer Drilling Co.

Lease Name Mease Well No. 1

Office Address Peoples Bank Bldg., ~~Wichita~~ Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-29 19 55

Application for plugging filed 1-29 19 55

Application for plugging approved 1-29 19 55

Plugging commenced 1-29 19 55

Plugging completed 1-29 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4907 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	243'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with mud to 240'. Plug set at 240' with 1/3 sack of hulls and 20 sacks of cement through drill pipe.
Hole filled to 40' with mud, top plug at 40' with 10 sacks cement

3
CONSERVATION DIVISION
Wichita, Kansas
01-31-1955

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Schafer Drilling Co.
Address Peoples Bank, Bldg, Pratt, Kansas

STATE OF Kansas, COUNTY OF Pratt, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Pratt, ks
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 1955
Maudie B Mc Bride
Notary Public.

My commission expires June 30, 1955

PLUGGING
FILE SEC 36 T. 30 R. 11 W
BOOK PAGE 94 LINE 20

15-007-00129-00-00

0-243	Surface Hole
243-940	Red Bed and Shells
940-1235	Shale and Shells
1235-1380	Salt
1380-1655	Shale and Shells
1655-1715	Lime and Shale
1715-1955	Lime
1955-3090	Lime and Shale
3090-3230	Lime and Sand
3230-3530	Lime and Shale
3530-3625	Shale and Shells
3625-3770	Lime and Shale
3770-3815	Shale and Sand
3815-4005	Lime and Shale
4005-4440	Lime
4440-4473	Chert
4473-4497	Chert - Lime and Shale
4497-4534	Lime and Shale
4534-4635	Shale and Shells
4635-4685	Shale
4685-4755	Lime
4755-4810	Sand and Shale
4810-4840	Lime, Sand and Shale
4840-4907	Shale and Lime
4907	TOTAL DEPTH

I certify that the above drillers log is true and correct as taken from the daily drilling reports of the Mease #1

H. Selby
Schaefer Drilling Co.

State of Kansas: County of Pratt: SS

The above subscribed and sworn to me this 29th day of January, 1955.

Maudie B McBride
Notary Puble

My commission expires June 30, 1955.

PLUGGING
FILE REC 36 T 30 R 11 W
BOOK PAGE 94 LINE 20

JAN 31 1955
CONSERVATION DIVISION
Wichita, Kansas
01-31-1955